

Wallbridge Martiniere Gold Project: 2025 Phase 1 Drillhole Information								
Drill Hole ID	Easting (NAD83)	Northing (NAD83)	Elevation (m)	Length (m)	EOH Depth (m)	Azimuth	Dip	VG ⁽¹⁾
MR-24-100_ext'n	642210	5543675	257	209	369	330	-45	VG
MR-24-110_ext'n	642600	5543145	257	305	471	360	-45	
MR-25-111	642365	5543120	256	558	558	360	-50	VG
MR-25-112	642130	5543365	258	501	501	10	-60	
MR-25-113	641725	5543675	258	489	489	350	-48	
MR-25-114	642500	5543600	257	351	351	350	-60	
MR-25-115	642640	5543800	257	252	252	360	-45	VG
MR-25-116	642600	5543145	257	477	477	360	-65	VG
MR-25-117	642945	5542975	254	399	399	360	-50	
MR-25-118	642690	5542565	256	300	300	360	-50	
MR-25-121	642235	5543161	257	651	651	355	-60	VG
⁽¹⁾ Drill holes containing visible gold ("VG"). ext'n = Extension drill hole.								

Wallbridge Martiniere Gold Project: 2025 Phase 1 Assay Summary ¹						
Drill Hole	VG ^{*2}	From (m)	To (m)	Length ³ (m)	Au ⁴ (g/t)	Zone/Corridor
MR-24-100		0.0	30.3	30.3		Overburden
		30.3	46.5	16.2	0.02	HORSEFLY
		46.5	47.6	1.1	3.66	HORSEFLY
		47.6	57.8	10.2	0.09	HORSEFLY
	*	57.8	68.8	11.0	16.21	HORSEFLY
	Including *	57.8	60.1	2.3	15.18	
		60.1	62.3	2.2	3.44	
		62.3	64.1	1.8	37.13	
		64.1	65.9	1.8	0.42	
		65.9	67.1	1.2	41.68	
		67.1	68.0	0.9	0.34	
		68.0	68.8	0.8	23.18	
		68.8	73.5	4.7	0.05	HORSEFLY
		73.5	74.1	0.6	0.84	HORSEFLY
		74.1	90.5	16.4	0.04	HORSEFLY
		90.5	91.0	0.5	1.09	HORSEFLY
		91.0	99.0	8.0	0.05	HORSEFLY
		99.0	100.2	1.2	1.34	HORSEFLY
		100.2	101.2	1.0	0.09	HORSEFLY
		101.2	102.1	0.9	0.61	HORSEFLY
		102.1	110.2	8.1	0.03	HORSEFLY
		110.2	111.2	1.0	2.30	HORSEFLY
		111.2	112.2	1.0	0.06	HORSEFLY
		112.2	114.4	2.2	0.74	HORSEFLY
	*	114.4	121.3	6.9	7.24	HORSEFLY
	Including	114.4	115.4	1.0	2.05	
	*	115.4	117.3	1.9	17.56	
		117.3	119.0	1.7	2.08	
	*	119.0	120.3	1.3	6.88	
		120.3	121.3	1.0	1.76	
		121.3	124.4	3.1	0.08	HORSEFLY
		124.4	130.0	5.6	3.70	HORSEFLY
	Including	124.4	124.9	0.5	3.18	
		124.9	125.5	0.6	20.10	
		125.5	127.7	2.2	0.28	
		127.7	130.0	2.3	2.45	
		130.0	131.0	1.0	0.54	HORSEFLY
		131.0	138.8	7.8	0.12	HORSEFLY
		138.8	139.8	1.0	0.72	HORSEFLY
		139.8	155.0	15.2	0.09	HORSEFLY
		155.0	155.5	0.5	10.80	HORSEFLY
		155.5	162.0	6.5	0.13	HORSEFLY

Wallbridge Martiniere Gold Project: 2025 Phase 1 Assay Summary ¹								
Drill Hole	VG* ²	From (m)	To (m)	Length ³ (m)	Au ⁴ (g/t)	Zone/Corridor		
		162.0	163.5	1.5	6.11	HORSEFLY		
		163.5	247.0	83.5	0.04	HORSEFLY		
		247.0	247.5	0.5	1.23	HORSEFLY		
		247.5	284.6	37.1	0.06	HORSEFLY		
		*	284.6	299.0	14.4	6.71	HORSEFLY	
		Including	284.6	286.5	1.9	5.08		
			286.5	288.0	1.5	0.04		
			288.0	291.0	3.0	9.81		
			291.0	294.0	3.0	0.14		
		*	294.0	299.0	5.0	11.41		
		*	299.0	327.0	28.0	0.07	HORSEFLY	
			327.0	327.5	0.5	4.29	HORSEFLY	
			327.5	355.0	27.5	0.06	HORSEFLY	
			355.0	356.0	1.0	1.37	HORSEFLY	
			356.0	364.0	8.0	0.13	HORSEFLY	
			364.0	365.0	1.0	1.15	HORSEFLY	
			365.0	369.0	4.0	0.13	HORSEFLY	
MR-24-110		0.0	33.8	33.8		Overburden		
		33.8	79.3	45.5	0.03	DRAGONFLY		
		79.3	80.6	1.3	17.35	DRAGONFLY		
		80.6	101.0	20.4	0.03	DRAGONFLY		
		101.0	102.5	1.5	0.72	DRAGONFLY		
		102.5	143.0	40.5	0.03	DRAGONFLY		
		*	143.0	145.3	2.3	27.60	DRAGONFLY	
		Including	143.0	143.6	0.6	9.99		
			*	143.6	144.3	0.7	86.30	
			144.3	145.3	1.0	2.16		
			145.3	234.2	88.9	0.02	DRAGONFLY	
			234.2	235.4	1.2	5.95	DRAGONFLY	
			235.4	321.0	85.6	0.02	DRAGONFLY	
321.0	323.6		2.6	0.78	DRAGONFLY			
323.6	471.0		147.4	0.04	DRAGONFLY			
MR-25-111			0.0	27.5	27.5		Overburden	
		27.5	61.8	34.3	0.03	DRAGONFLY		
		61.8	63.0	1.2	1.80	DRAGONFLY		
		63.0	74.0	11.0	0.07	DRAGONFLY		
		74.0	75.0	1.0	1.01	DRAGONFLY		
		75.0	114.0	39.0	0.02	DRAGONFLY		
		114.0	115.0	1.0	2.59	DRAGONFLY		
		115.0	152.0	37.0	0.05	DRAGONFLY		
		152.0	153.0	1.0	0.65	DRAGONFLY		
		153.0	284.0	131.0	0.03	DRAGONFLY		

Wallbridge Martiniere Gold Project: 2025 Phase 1 Assay Summary ¹						
Drill Hole	VG* ²	From (m)	To (m)	Length ³ (m)	Au ⁴ (g/t)	Zone/Corridor
	*	284.0	285.0	1.0	2.19	DRAGONFLY
		285.0	457.0	172.0	0.03	DRAGONFLY
		457.0	458.5	1.5	7.87	DRAGONFLY
		457.0	458.0	1.0	0.50	
		458.0	458.5	0.5	22.60	
		458.5	461.0	2.5	0.10	DRAGONFLY
		461.0	462.0	1.0	2.16	DRAGONFLY
		462.0	463.0	1.0	0.28	DRAGONFLY
		463.0	464.0	1.0	0.52	DRAGONFLY
		464.0	467.7	3.7	3.98	DRAGONFLY
	464.0	467.0	3.0	2.79		
	467.0	467.7	0.7	9.08		
	467.7	500.7	33.0	0.06	DRAGONFLY	
	500.7	503.0	2.3	40.99	DRAGONFLY	
	500.7	502.2	1.5	59.60		
	502.2	503.0	0.8	6.11		
	503.0	541.4	38.4	0.05	DRAGONFLY	
	541.4	541.9	0.5	0.47	DRAGONFLY	
	541.9	545.5	3.6	0.04	DRAGONFLY	
	545.5	546.5	1.0	1.07	DRAGONFLY	
	546.5	549.0	2.5	0.06	DRAGONFLY	
	549.0	551.0	2.0	0.55	DRAGONFLY	
	551.0	555.2	4.2	0.05	DRAGONFLY	
	555.2	556.0	0.8	0.66	DRAGONFLY	
	556.0	558.0	2.0	0.06	DRAGONFLY	
MR-25-112	*	0.0	47.9	47.9		Overburden
		47.9	97.0	49.1	0.04	DRAGONFLY
		97.0	97.8	0.8	2.05	DRAGONFLY
		97.8	140.0	42.2	0.04	DRAGONFLY
		140.0	141.0	1.0	0.77	DRAGONFLY
		141.0	253.0	112.0	0.02	DRAGONFLY
		253.0	254.0	1.0	0.89	DRAGONFLY
		254.0	254.7	0.7	0.25	DRAGONFLY
		254.7	257.4	2.7	20.91	DRAGONFLY
		254.7	255.5	0.8	3.52	
	255.5	256.5	1.0	51.90		
	256.5	257.4	0.9	1.93		
	257.4	261.0	3.6	0.05	DRAGONFLY	
	261.0	262.0	1.0	0.87	DRAGONFLY	
	262.0	398.7	136.7	0.05	DRAGONFLY	
	398.7	400.0	1.3	0.93	DRAGONFLY	
	400.0	446.0	46.0	0.03	DRAGONFLY	

Wallbridge Martiniere Gold Project: 2025 Phase 1 Assay Summary ¹						
Drill Hole	VG* ²	From (m)	To (m)	Length ³ (m)	Au ⁴ (g/t)	Zone/Corridor
		446.0	447.2	1.2	1.00	DRAGONFLY
		447.2	470.0	22.8	0.07	DRAGONFLY
		470.0	471.0	1.0	0.53	DRAGONFLY
		471.0	501.0	30.0	0.01	DRAGONFLY
MR-25-113		0.0	19.8	19.8		Overburden
		19.8	25.5	5.7	0.04	BUG LAKE NORTH
		25.5	30.0	4.5	1.14	BUG LAKE NORTH
		25.5	27.0	1.5	0.22	
		27.0	27.6	0.6	6.14	
		27.6	30.0	2.4	0.46	
		30.0	111.9	81.9	0.03	BUG LAKE NORTH
		111.9	112.4	0.5	2.71	BUG LAKE NORTH
		112.4	292.3	179.9	0.02	BUG LAKE NORTH
		292.3	293.8	1.5	1.79	BUG LAKE NORTH
		293.8	305.2	11.4	0.12	BUG LAKE NORTH
		305.2	309.0	3.8	0.54	BUG LAKE NORTH
		309.0	314.0	5.0	0.11	BUG LAKE NORTH
		314.0	315.5	1.5	0.80	BUG LAKE NORTH
		315.5	328.4	12.9	0.09	BUG LAKE NORTH
		328.4	329.1	0.7	2.02	BUG LAKE NORTH
		329.1	330.0	0.9	0.21	BUG LAKE NORTH
		330.0	330.5	0.5	0.67	BUG LAKE NORTH
		330.5	381.0	50.5	0.03	BUG LAKE NORTH
		381.0	381.7	0.7	2.34	BUG LAKE NORTH
		381.7	387.4	5.7	0.44	BUG LAKE NORTH
		387.4	390.3	2.9	0.05	BUG LAKE NORTH
		390.3	392.0	1.7	2.41	BUG LAKE NORTH
		390.3	391.0	0.7	5.62	
		391.0	392.0	1.0	0.17	
		392.0	471.6	79.6	0.03	BUG LAKE NORTH
		471.6	473.0	1.4	0.60	BUG LAKE NORTH
		473.0	489.0	16.0	0.05	BUG LAKE NORTH
MR-25-114		0.0	21.0	21.0		Overburden
		21.0	226.7	205.7	0.01	HORSEFLY
		226.7	227.6	0.9	2.79	HORSEFLY
		227.6	240.7	13.1	0.24	HORSEFLY
		240.7	241.5	0.8	2.05	HORSEFLY
		241.5	242.4	0.9	0.22	HORSEFLY
		242.4	243.3	0.9	0.57	HORSEFLY
		243.3	351.0	107.7	0.02	HORSEFLY
MR-25-115	*	0.0	18.0	18.0		Overburden
		18.0	231.0	213.0	0.01	MARTINIERE NORTHEAST

Wallbridge Martiniere Gold Project: 2025 Phase 1 Assay Summary ¹					
Drill Hole	VG* ²	From (m)	To (m)	Length ³ (m)	Au ⁴ (g/t) Zone/Corridor
	<i>Including</i>	231.0	232.5	1.5	0.71 MARTINIERE NORTHEAST
		232.5	234.0	1.5	0.10 MARTINIERE NORTHEAST
		234.0	237.0	3.0	7.27 MARTINIERE NORTHEAST
		234.0	235.5	1.5	8.16
		235.5	237.0	1.5	6.38
		237.0	252.0	15.0	0.02 MARTINIERE NORTHEAST
MR-25-116		0.0	27.5	27.5	Overburden
		27.5	38.5	11.0	0.03 DRAGONFLY
		38.5	39.0	0.5	0.59 DRAGONFLY
		39.0	39.5	0.5	3.32 DRAGONFLY
		39.5	71.8	32.3	0.02 DRAGONFLY
		71.8	73.0	1.2	0.89 DRAGONFLY
		73.0	95.0	22.0	0.02 DRAGONFLY
		95.0	96.0	1.0	0.78 DRAGONFLY
		96.0	105.0	9.0	0.03 DRAGONFLY
		105.0	106.0	1.0	0.65 DRAGONFLY
		106.0	160.8	54.8	0.03 DRAGONFLY
		* 160.8	162.0	1.2	28.44 DRAGONFLY
		<i>Including</i> 160.8	161.4	0.6	4.08
		* 161.4	162.0	0.6	52.80
		162.0	162.5	0.5	0.50 DRAGONFLY
		162.5	212.4	49.9	0.05 DRAGONFLY
		212.4	213.0	0.6	0.84 DRAGONFLY
		213.0	326.0	113.0	0.03 DRAGONFLY
		326.0	327.0	1.0	0.77 DRAGONFLY
		327.0	329.0	2.0	0.36 DRAGONFLY
		329.0	329.5	0.5	5.78 DRAGONFLY
		329.5	336.0	6.5	0.10 DRAGONFLY
		336.0	340.0	4.0	18.54 DRAGONFLY
		<i>Including</i> 336.0	337.1	1.1	5.49
		337.1	338.0	0.9	0.48
		338.0	339.0	1.0	65.80
		339.0	340.0	1.0	1.88
		340.0	463.0	123.0	0.03 DRAGONFLY
		463.0	464.0	1.0	0.83 DRAGONFLY
		464.0	477.0	13.0	0.02 DRAGONFLY
MR-25-117		0.0	17.6	17.6	Overburden
		17.6	154.8	137.2	0.01 DRAGONFLY
		154.8	157.0	2.2	1.09 DRAGONFLY
		157.0	159.0	2.0	0.07 DRAGONFLY
		159.0	160.5	1.5	0.56 DRAGONFLY
		160.5	274.5	114.0	0.04 DRAGONFLY

Wallbridge Martiniere Gold Project: 2025 Phase 1 Assay Summary ¹						
Drill Hole	VG* ²	From (m)	To (m)	Length ³ (m)	Au ⁴ (g/t)	Zone/Corridor
		274.5	276.6	2.1	7.61	DRAGONFLY
	Including	274.5	275.0	0.5	0.11	
		275.0	275.9	0.9	17.60	
		275.9	276.6	0.7	0.13	
		276.6	399.0	122.4	0.0	DRAGONFLY
MR-25-118		0.0	18.3	18.3		Overburden
		18.3	72.9	54.6	0.01	BUG LAKE SOUTH
		72.9	73.5	0.6	0.72	BUG LAKE SOUTH
		73.5	189.9	116.4	0.02	BUG LAKE SOUTH
		189.9	190.9	1.0	2.35	BUG LAKE SOUTH
		190.9	263.5	72.6	0.04	BUG LAKE SOUTH
		263.5	265.0	1.5	1.03	BUG LAKE SOUTH
		265.0	300.0	35.0	0.06	BUG LAKE SOUTH
MR-25-119		Assays Pending				
MR-25-120		Assays Pending				
MR-25-121		0.0	65.2	65.2		Overburden
		65.2	87.0	21.8	0.01	DRAGONFLY
		87.0	90.5	3.5	C.N.R.	DRAGONFLY
		90.5	121.2	30.7	0.01	DRAGONFLY
	*	121.2	123.0	1.8	28.52	DRAGONFLY
	Including	121.2	122.2	1.0	0.94	
		122.2	123.0	0.8	63.00	
		123.0	247.0	124.0	0.02	DRAGONFLY
	*	247.0	248.5	1.5	14.31	DRAGONFLY
	Including *	247.0	247.7	0.7	30.50	
		247.7	248.5	0.8	0.15	
		248.5	249.1	0.6	0.02	DRAGONFLY
		249.1	250.5	1.4	0.50	DRAGONFLY
		250.5	375.4	124.9	0.02	DRAGONFLY
	*	375.4	378.8	3.4	5.79	DRAGONFLY
	Including	375.4	376.4	1.0	3.35	
		376.4	377.8	1.4	0.50	
	*	377.8	378.8	1.0	15.65	
		378.8	421.2	42.4	0.04	DRAGONFLY
		421.2	423.5	2.3	4.88	DRAGONFLY
	Including	421.2	422.2	1.0	10.30	
		422.2	423.5	1.3	0.71	
		423.5	443.9	20.4	0.06	DRAGONFLY
		443.9	454.0	10.1	16.79	DRAGONFLY
	Including	443.9	447.9	4.0	17.62	
		447.9	451.0	3.1	0.15	
		451.0	454.0	3.0	32.87	

Wallbridge Martiniere Gold Project: 2025 Phase 1 Assay Summary ¹						
Drill Hole	VG* ²	From (m)	To (m)	Length ³ (m)	Au ⁴ (g/t)	Zone/Corridor
		454.0	460.2	6.2	0.12	DRAGONFLY
		460.2	461.0	0.8	0.52	DRAGONFLY
		461.0	465.5	4.5	0.07	DRAGONFLY
		465.5	467.8	2.3	3.65	DRAGONFLY
	Including	465.5	466.8	1.3	0.41	
		466.8	467.8	1.0	7.87	
		467.8	480.0	12.2	0.09	DRAGONFLY
		480.0	482.4	2.4	2.65	DRAGONFLY
	Including	480.0	480.8	0.8	1.42	
		480.8	481.8	1.0	4.29	
		481.8	482.4	0.6	1.57	
		482.4	484.8	2.4	0.11	DRAGONFLY
		484.8	486.5	1.7	17.08	DRAGONFLY
	Including	484.8	485.5	0.7	38.90	
		485.5	486.5	1.0	1.01	
		486.5	487.5	1.0	0.52	DRAGONFLY
		487.5	554.3	66.8	0.03	DRAGONFLY
		554.3	555.6	1.3	0.71	DRAGONFLY
		555.6	570.4	14.8	0.03	DRAGONFLY
		570.4	571.0	0.6	6.98	DRAGONFLY
		571.0	577.0	6.0	0.06	DRAGONFLY
		577.0	579.0	2.0	8.90	DRAGONFLY
	Including	577.0	578.5	1.5	1.77	
		578.5	579.0	0.5	30.30	
		579.0	582.0	3.0	0.10	DRAGONFLY
		582.0	583.5	1.5	0.75	DRAGONFLY
		583.5	651.2	67.7	0.07	DRAGONFLY

Notes

- 1 Summarized assay highlights have been selected based on a combination of criteria including observable mineralization and/or having a Metal Factor ≥ 5 gm*m (MF = Au g/t * Interval length).
- 2 Asterisk * denotes visible gold (VG) observed in drill core.
- 3 True widths are estimated to be 60-90% of the reported core length intervals.
- 4 Grey background notes previously reported results (November 6, 2024 News Release) including updated results for those that were initially reported as >10g/t.
C.N.R.: Core Not Recovered.